Mobile PRO Systems
Smarter Solutions for Remote Applications

DATE: 4/17/2024

QUOTE #: 27638-B
QUOTE EXP: 5/18/2024
PROJECT NAME: San Mateo Police Dept

TO: San Mateo Police Dept
Anthony Riccardi
200 Franklin Parkway
San Mateo, CA 94403
650-255-2386
ariccardi@cityofsanmateo.org

QUOTE
27638-B

Qty. 2 - Falcon 3100 Video Surveillance Trailers

(Configured with Verkada Camera and Audio Systems)

Quote Revision 'A' : Quote Date Change Only
Quote Revision 'B' : Sales Tax Added

SALES PERSON	PROJECT SCOPE		PAYMENT TERMS
S.Dunker	Falcon 3100 Video Surveillance Trailer		NET 30
QTY	**DESCRIPTION**	**UNIT PRICE**	**EXTENDED PRICE**
2	MPS 3100 TRAILER SYSTEM	**$54,900.00**	**$109,800.00**

QTY	MODEL NUMBER	DESCRIPTION	
1	MPS-3100-BASE	**FALCON 3100 BASE TRAILER SYSTEM w/ 20 ft. stabilized MAST**	*Base System Includes MP Status*
1	GEN-3100-GAS	MPS 3100 **GAS GENERATOR** SYSTEM (recommended)	*Monitoring & Control Platform*
1	BATT-KIT-9-100	800 AH AGM BATT 3100	*- Door Contact, Vibration Sensor & GPS*
2	PTZ-CP52-512-VERK	***PTZ Camera - VERKADA CP52 512GB 30 days***	*(2) Verkada PTZ Cameras*
1	FC-CF81-512-VERK	***FIXED Camera - VERKADA CF81-E 512GB 30 days***	*(1) Verkada Fisheye Fixed Camera*
2	POE-70W-24V	24VDC DUAL CHANNEL HI POE 70W	
2	POE-35W-24V	24VDC HI POE 35W	
2	POE-RACK-PLATE	RACK PLATE WITH MOUNTING HARWARE	
1	TR-CAM-MOUNT	STOCK CAMERA MOUNT	
2	TR-CM-AXIS	CAMERA MOUNT W/AXIS HUB	
3	VMS-CAMLIC-VERKADA	***VERKADA CAMERA License - 1 year***	*Verkada License*
1	VMS-HORNLIC-VERKADA	***VERKADA HORN License - 1 year***	*Verkada License*
1	COM-TR-CP-IBR600	**CRADLEPOINT CELLULAR ROUTER IBR600 KIT**	*Celluar Modem 4G with WIFI*
1	3100-TR-AUDIO-VERK	***VERKADA Audio Kit - BZ11 Horn/Speaker***	
1	3100-TR-AUDIO-MT	Audio Kit Mounting System	
1	SW-16-P-1GIG	16 PORT NETWORK SWITCH	
1	TM-STROBE POD KIT	***TOP MAST LED STROBE LIGHT POD KIT***	*LED Strobe Light - Top of Mast*
1	TM-LIGHT-BAR-KIT-42-R20	***TOP MAST 2-42" LED FLOOD LIGHT KIT***	*LED Flood Lights - Top of Mast*
1	HD-WHEEL-JACK	HEAVY DUTY FRONT WHEEL JACK	
1	3100-HIGH-PIR 402	***TOP-MAST MOTION (3 PIR) OPTEX LX-402 KIT***	*(3) Motion Sensors - Top of Mast*
1	SOLAR-900W -3100	***900W SOLAR SYSTEM 3100 KIT***	*Solar Charging*

System Includes a (1) One Year Limited Warranty
This QUOTE is valid for 30 days.

Total Less Options:	**$109,800.00**
Sales Tax (9.625%):	**$10,568.25**
Estimated Shipping:	**$4,900.00**
Estimate TOTAL:	**$125,268.25**

PROPOSAL CREATED BY:
Steve Dunker
V.P. of Business Development
Mobile Pro Systems
250 Lothenbach Ave.
West St. Paul MN 55118
Cell: 612-619-8018 Direct: 952-324-5645
eMail: Steve.Dunker@MobileProSystems.com

Freight Charges covers two (2) trailers shipped to San Mateo, CA…..
NOTE: Video storage is included within the cameras themselves. There is NO Video Server located within trailer with this configuration.

I accept this estimate **DATE**